S.N	Description of work	Unit	No.	L	B	D	QTY	Rate	Amount
	DEDUCTIONS FOR LINTEL								
	ED		-1	4.10		0.15	-0.62		
	D		-3	1.80		0.15	-0.81		
	D1		-4	1.50		0.15	-0.90		
	W		-1	2.40		0.15	-0.36		
	W1		-8	1.80		0.15	-2.16		
	V		-10	1.20		0.15	-1.80	984.96	255163.64
							259.06		
	Basic Rate =		912.00						
	Area Weightage @ 8% =		72.96						
	Total Rate per Unit =		984.96						
	FIRST FLOOR	SQM							
	Horizontal walls		3	19.64		2.55	150.25		
	Horizontal walls		1	10.94		2.55	27.90		
	Vertical walls		2	11.86		2.55	60.51		
	Vertical walls		7	4.40		2.55	78.54		
	Vertical walls		1	4.00		2.55	10.20		
	DEDUCTIONS								
	FOR FIRST FLOOR								
	D		-1	1.20		2.10	-2.52		
	D1		-6	0.90		2.10	-11.34		
	W1		-15	1.20		1.35	-24.30		
	V		-8	0.60		0.45	-2.16		
	DEDUCTIONS FOR LINTEL								
	D		-1	1.80		0.15	-0.27		
	D1		-6	1.50		1.15	-10.35		
	W1		-15	1.80		0.15	-4.05		
	V		-8	1.20		0.15	-1.44		
							270.96	1022.76	277126.44
	Basic Rate =		912.00						
	Lift charges=		35.00						
	Area Weightage @ 8% =		75.76						
	Total Rate per Unit =		1022.76						
	SECOND FLOOR	SQM							
	Horizontal walls		3	19.64		2.55	150.25		
	Horizontal walls		1	10.94		2.55	27.90		
	Horizontal walls		1	3.30		2.55	8.42		
	Vertical walls		2	11.86		2.55	60.49		
	Vertical walls		5	4.40		2.55	56.10		
	Vertical walls		1	4.00		2.55	10.20		
	DEDUCTIONS								
	FOR FIRST FLOOR								
	D		-2	1.20		2.10	-5.04		
	D1		-4	0.90		2.10	-7.56		
	W1		-15	1.20		1.35	-24.30		
	V		-10	0.60		0.45	-2.70		
	DEDUCTIONS FOR LINTEL								
	D		-2	1.80		0.15	-0.54		
	D1		-4	1.50		1.15	-6.90		
	W1		-15	1.80		0.15	-4.05		
	V		-10	1.20		0.15	-1.80		

Scanned by TapScanner

S.N	Description of work	Unit	No.	L	B	D	Qty	Rate	Amount
							260.45	1060.56	276227.09
	Basic Rate =	912.00							
	Lift charges=	70.00							
	Area Weightage @ 8% =	78.56							
	Total Rate per Unit =	1060.56							
	Head Room	SQM							
	Horizontal walls		2	4.90		2.55	24.99		
	Vertical walls		2	3.65		2.55	18.62		
	DEDUCTIONS								
	FOR Head Room								
	D		-2	0.90		2.10	-3.78		
	DEDUCTIONS FOR LINTEL								
	D		-2	1.50		0.15	-0.45		
							39.38	1098.36	43247.93
	Basic Rate =	912.00							
	Lift charges=	105.00							
	Area Weightage @ 8% =	81.36							
	Total Rate per Unit =	1098.36							
16	KSRB 5-14.1 : **Providing and constructing percast concrete solid blocks** with compressive strength not less than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, jamb closer blocks) with solid concrete blocks of size **40x15x20cms** conforming to I.S : 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. **(P.No.27 I.No.5.27.2 of PWD SR 2018-19)**								
	OR								
	Providing and constructing mud blocks in superstructure including cost of materils, labours charges,scafolding,curing,complete as per specification.								
	GROUND FLOOR	SQM							
	Horizontal walls		3	2.50		2.55	19.13		
	Horizontal walls		2	2.60		2.55	13.26		
	Vertical walls		4	1.50		2.55	15.30		
	Vertical walls		1	3.50			8.93		
	DEDUCTIONS								
	FOR GROUND FLOOR								
	D2		-7	0.75		2.10	-11.03		
	DEDUCTIONS FOR LINTEL								
	D2		-7	1.35		0.15	-1.42		
							44.17	1029.24	45458.96
	Basic Rate =	953.00							
	Area Weightage @ 8% =	76.24							
	Total Rate per Unit =	1029.24							
	FIRST FLOOR	SQM							
	Horizontal walls		3	2.30		2.55	17.60		
	Horizontal walls		3	1.80		2.55	13.77		
	Vertical walls		6	1.50		2.55	22.95		
	DEDUCTIONS								
	FOR FIRST FLOOR								
	D2		-6	0.75		2.10	-9.45		
	DEDUCTIONS FOR LINTEL								
	D2		-6	1.35		0.15	-1.22		
							43.65	1067.04	46576.30
	Basic Rate =	953.00							
	Lift charges=	35.00							
	Area Weightage @ 8% =	79.04							

Scanned by TapScanner

S.N	Description of work	Unit	No.	L	B	D	Qty	Rate	Amount
	Total Rate per Unit =	1067.04							
	SECOND FLOOR	SQM							
	Horizontal walls		4	2.30		2.55	23.46		
	Horizontal walls		3	1.80		2.55	13.77		
	Vertical walls		7	1.50		2.55	26.78		
	DEDUCTIONS								
	FOR FIRST FLOOR								
	D2		-7	0.75		2.10	-11.03		
	DEDUCTIONS FOR LINTEL								56968.31
	D2		-7	1.35		0.15	-1.42	1104.84	
							51.56		
	Basic Rate =	953.00							
	Lift charges=	70.00							
	Area Weightage @ 8% =	81.84							
	Total Rate per Unit =	1104.84							
	PARAPET WALL	SQM					35.53		
	Horizontal walls		2	19.74		0.90	21.35		64993.36
	Vertical walls		2	11.86		0.90	56.88	1142.64	
	Basic Rate =	953.00							
	Lift charges=	105.00							
	Area Weightage @ 8% =	84.64							
	Total Rate per Unit =	1142.64							
17	KSRB 4.2.7 : Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs. with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum. with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008. machine mixed. concrete laid in layers not exceeding 15 cms thick. vibrated for all works in ground floor level for roof slabs. staircase. lintles and beams retaining walls. return walls. walls (any thickness) including attached pilasters. columns. .pillars. posts. struts. buttresses. string or lacing courses. parapets. coping. bed blocks. anchor blocks. plain window cills. fillets etc.. including cost of all materials. labour. HOM of machinery. curing. complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1. 4.6 **(PWD -SR 2018-19. P-14.** I-4.12)									
Ground Floor	Cum								
Window cill							0.04		
W		1	2.40	0.20	0.075		0.22		
W1		8	1.80	0.20	0.075		0.18		
V		10	1.20	0.20	0.075				
Basic Rate =	6045.00						0.43	6528.60	2820.36
Area Weightage @ 8% =	483.60								
Total Rate per Unit =	6528.60								
First Floor	Cum								
Window cill							0.41		
W1		15	1.80	0.20	0.075		0.14		
V		8	1.20	0.20	0.075				
Basic Rate =	6045.00								
Lift charges=	60.00						0.55	6593.40	3619.78
Area Weightage @ 8% =	488.40								
Total Rate per Unit =	6593.40								
Second Floor	Cum								
Window cill									

Scanned by TapScanner

S.N	Description of work	Unit	No.	L	B	D	Qty	Rate	Amount
	W1		15	1.80	0.20	0.075	0.41		
	V		10	1.20	0.20	0.075	0.18		
	Basic Rate =	6045.00							
	Lift charges=	120.00							
	Area Weightage @ 8% =	493.20							3895.05
	Total Rate per Unit =	6658.20					0.59	6658.20	
18	KSRB 4.2.7 : Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintles and beams retaining walls, return walls, walls (any thickness) including attached pilasters, columns, .pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1, 4.6 (PWD -SR 2018-19, P-14, 1-4.12)								
		Cum							
	FOR LINTEL GROUND FLOOR								
	ED		1	4.10	0.20	0.15	0.12		
	D		3	1.80	0.20	0.15	0.16		
	D1		4	1.50	0.20	0.15	0.18		
	D2		7	1.35	0.15	0.15	0.21		
	W		1	2.40	0.20	0.15	0.07		
	W1		8	1.80	0.20	0.15	0.43		
	V		10	1.20	0.20	0.15	0.36		
						Sub Total	1.54	6528.60	10064.65
	Basic Rate =	6045.00							
	Area Weightage @ 8% =	483.60							
	Total Rate per Unit =	6528.60							
	FOR LINTEL FIRST FLOOR								
	D		1	1.80	0.20	0.15	0.05		
	D1		6	1.50	0.20	0.15	0.27		
	W1		15	1.80	0.20	0.15	0.81		
	V		8	1.20	0.20	0.15	0.29		
	D2		6	1.35	0.15	0.15	0.18		
						Sub Total	1.60	6593.40	10577.46
	Basic Rate =	6045.00							
	Lift charges=	60.00							
	Area Weightage @ 8% =	488.40							
	Total Rate per Unit =	6593.40							
	FOR LINTEL SECOND FLOOR								
	D		2	1.80	0.20	0.15	0.11		
	D1		4	1.50	0.20	0.15	0.18		
	W1		15	1.80	0.20	0.15	0.81		
	V		10	1.20	0.20	0.15	0.36		
	D2		7	1.35	0.15	0.15	0.21		
						Sub Total	1.67	6658.20	11123.36
	Basic Rate =	6045.00							
	Lift charges=	120.00							
	Area Weightage @ 8% =	493.20							
	Total Rate per Unit =	6658.20							
	FOR LINTEL HEAD ROOM								
	D		2	1.80	0.20	0.15	0.11		
						Sub Total	0.11	6723.00	726.08
	Basic Rate =	6045.00							

Scanned by TapScanner

S.N	Description of work	Unit	No.	L	B	D	Qty	Rate	Amount
	Lift charges=		180.00						
	Area Weightage @ 8% =		498.00						
	Total Rate per Unit =		6723.00						
19	KSRB 4.6.7: Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for sides and soffits of beams, beam haunchings, cantilever, girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (P.No.17 I.No.4.34 of PWD S.R 2018-19)								
	GROUND FLOOR	Sqm							
	LINTEL SIDES								
	ED		2	4.10		0.15	1.23		
	D		6	1.80		0.15	1.62		
	D1		8	1.50		0.15	1.80		
	D2		14	1.35		0.15	2.835		
	W		2	2.4		0.15	0.72		
	W1		16	1.8		0.15	4.32		
	V		20	1.2		0.15	3.6		
	LINTEL BOTTOM								
	ED		1	4.10	0.20		0.82		
	D		3	1.80	0.20		1.08		
	D1		4	1.50	0.20		1.20		
	D2		7	1.35	0.15		1.42		
	W		1	2.40	0.15		0.36		
	W1		8	1.80	0.15		2.16		
	V		10	1.20	0.15		1.80		
							24.96	315.36	7872.17
	Basic Rate =	292.00							
	Area Weightage @ 8% =	23.36							
	Total Rate per Unit =	315.36							
	FIRST FLOOR	Sqm							
	LINTEL SIDES								
	D		2	1.80		0.15	0.54		
	D1		12	1.50		0.15	2.70		
	W1		30	1.80		0.15	8.10		
	V		16	1.20		0.15	2.88		
	D2		12	1.35		0.15	2.43		
	LINTEL BOTTOM								
	D		1	1.80	0.20		0.36		
	D1		6	1.50	0.20		1.80		
	W1		15	1.80	0.20		5.40		
	V		8	1.20	0.20		1.92		
	D2		6	1.35	0.15		1.22		
	Basic Rate =	292.00					27.35	342.36	9361.83
	Lift charges=	25.00							

Scanned by TapScanner

S.N	Description of work	Unit	No.	L	B	D	Qty	Rate	Amount
	Area Weightage @ 8% =		25.36						
	Total Rate per Unit =		342.36						
	SECOND FLOOR	Sqm							
	LINTEL SIDES								
	D		4	1.80		0.15	1.08		
	D1		8	1.50		0.15	1.80		
	W1		30	1.80		0.15	8.10		
	V		20	1.20		0.15	3.60		
	D2		14	1.35		0.15	2.84		
	LINTEL BOTTOM								
	D		2	1.50	0.20		0.60		
	D1		4	1.50	0.20		1.20		
	W1		15	1.80	0.20		5.40		
	V		10	1.20	0.20		2.40		
	D2		7	1.35	0.15		1.42		
							28.43	369.36	10501.83
	Basic Rate =	292.00							
	Lift charges=	50.00							
	Area Weightage @ 8% =	27.36							
	Total Rate per Unit =	369.36							
	HEAD ROOM	Sqm							
	LINTEL SIDES								
	D		4	1.50		0.15	0.90		
	LINTEL BOTTOM								
	D		4	1.50	0.20		1.20		
							2.10	396.36	832.36
	Basic Rate =	292.00							
	Lift charges=	75.00							
	Area Weightage @ 8% =	29.36							
	Total Rate per Unit =	396.36							
20	KSRB 4.2.11 : Providing and laying in position reinforced cement concrete of design Mix M20 with OPC @ 27.20kgs. with 12mm and down size graded granite metal coarse aggregates @0.05865cum and fine aggregtes @ 0.0391cum. with superplastisiser @0.225lts. machine mixed. **well compacted for plain chajja of 8.5 cms.** average thickness. upto ground floor level. including cost of all materials. labour. HOM finishing. curing. complete but excluding cost of reinforcement as per specifications. Specification **No. KBS 4.1, 4.6 (P.No.16, I.No.4.20 of PWD S.R 2018-19)**									
	Ground Floor Chajja	Sqm							
	W		1	2.40	0.60		1.44		
	W1		8	1.80	0.60		8.64		
							10.08	535.68	5400.00
	Basic Rate =	496.00							
	Area Weightage @ 8% =	39.68							
	Total Rate per Unit =	535.68							
	First Floor Chajja	Sqm							

Scanned by TapScanner

S.N	Description of work	Unit	No.	L	B	D	Qty	Rate	Amount
	W1		15	1.80	0.60	0.10	1.62	542.16	878.00
							1.62		
	Basic Rate =	496.00							
	Lift charges=	6.00							
	Area Weightage @ 8% =	40.16							
	Total Rate per Unit =	542.16							
	Second Floor Chajja	Sqm							
	W1		15	1.80	0.60		16.20	548.64	8888.00
							16.20		
	Basic Rate =	496.00							
	Lift charges=	12.00							
	Area Weightage @ 8% =	40.64							
	Total Rate per Unit =	548.64							
21	KSRB 4-6.10: Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels etc.. including edges including cost of all materials, labour complete as per specification. Specification No.KBS 4.6.2 (P.No.17, I.No.4.37 of PWD - SR 2018-19)								
	Ground Floor Chajja	Sqm					1.44		3516.31
	W		1	2.40	0.60		8.64	348.84	
	W1		8	1.80	0.60		10.08		
	Basic Rate =	323.00							
	Area Weightage @ 8% =	25.84							
	Total Rate per Unit =	348.84							
	First Floor Chajja	Sqm					16.20	355.32	5756.18
	First Floor Chajja		15	1.80	0.60		16.20		
	Basic Rate =	323.00							
	Lift charges=	6.00							
	Area Weightage @ 8% =	26.32							
	Total Rate per Unit =	355.32							
	Second Floor Chajja	Sqm					16.20	361.80	5861.16
			15	1.80	0.60		16.20		
	Basic Rate =	323.00							
	Lift charges=	12.00							
	Area Weightage @ 8% =	26.80							
	Total Rate per Unit =	361.80							
22	Providing and laying in position cement concrete using 25mm and down size granite coarse aggregate and fine aggregate of ready mix concrete for RCC works laid 15cm thick layers and well compacted including vibrating curing etc.. including smoth finish in CM 1:3. with all lead and lift.'complete. (exclusive of cost of steel fabrication charges) -Ready mixed cement concrete for Beams.columns stairecase and roof with M-25(1:1:2) (Cement-320Kg/cum) Pages 19: item 4.49.2 @ P.W.D SR-2018-19)								
	GROUND FLOOR BEAMS	Cum					1.77		
	B1-B4		1	19.64	0.200	0.450	1.77		
	B5-B7		1	10.74	0.200	0.450	0.97		
	B8-B9		1	4.90	0.200	0.450	0.44		
	B10 TO B11		1	19.64	0.200	0.450	1.77		
	B12 TO B16		1	5.80	0.200	0.450	0.52		
	B17		1	11.86	0.200	0.450	1.07		
	B18 TO B20		1	4.40	0.200	0.450	0.40		
	B21								

Scanned by TapScanner

S.N	Description of work	Unit	No.	L	B	D	Qty	Rate	Amount
	B22-B23		1	6.86	0.200	0.450	0.62		
	B24		1	4.40	0.200	0.450	0.40		
	B25		1	4.40	0.200	0.450	0.40		
	B26 TO B27		1	6.86	0.200	0.450	0.62		
	B28 TO B28A		1	5.50	0.200	0.450	0.50		
	B29 TOB31		1	11.86	0.200	0.450	1.07		
	B32 TO B34		1	13.71	0.200	0.450	1.23		
	Basic Rate =	5497.00					13.52	5936.76	80258.46
	Area Weightage @ 8% =	439.76							
	Total Rate per Unit =	5936.76							
	FIRST FLOOR BEAMS	Cum							
	B1-B4		1	19.64	0.200	0.450	1.77		
	B5-B7		1	19.64	0.200	0.450	1.77		
	B8-B9		1	10.74	0.200	0.450	0.97		
	B10 TO B11		1	4.90	0.200	0.450	0.44		
	B12 TO B16		1	19.64	0.200	0.450	1.77		
	B18 TO B20		1	11.86	0.200	0.450	1.07		
	B21		1	4.40	0.200	0.450	0.40		
	B22-B23		1	6.86	0.200	0.450	0.62		
	B24		1	4.40	0.200	0.450	0.40		
	B25		1	4.40	0.200	0.450	0.40		
	B26 TO B27		1	6.86	0.200	0.450	0.62		
	B28A		1	3.65	0.200	0.450	0.33		
	B29 TOB31		1	11.86	0.200	0.450	1.07		
	B32A TO B34		1	11.86	0.200	0.450	1.07		
	Basic Rate =	5497.00					12.66	5936.76	75182.53
	Area Weightage @ 8% =	439.76							
	Total Rate per Unit =	5936.76							
	SECOND FLOOR BEAMS	Cum							
	B1-B4		1	19.64	0.200	0.450	1.77		
	B5-B7		1	19.64	0.200	0.450	1.77		
	B8-B9		1	10.74	0.200	0.450	0.97		
	B10 TO B11		1	4.90	0.200	0.450	0.44		
	B12 TO B16		1	19.64	0.200	0.450	1.77		
	B18 TO B20		1	11.86	0.200	0.450	1.07		
	B21		1	4.40	0.200	0.450	0.40		
	B22-B23		1	6.86	0.200	0.450	0.62		
	B24		1	4.40	0.200	0.450	0.40		
	B25		1	4.40	0.200	0.450	0.40		
	B26 TO B27		1	6.86	0.200	0.450	0.62		
	B28A		1	3.65	0.200	0.450	0.33		
	B29 TOB31		1	11.86	0.200	0.450	1.07		
	B32A TO B34		1	11.86	0.200	0.450	1.07		
	Basic Rate =	5497.00					12.66	5936.76	75182.53
	Area Weightage @ 8% =	439.76							
	Total Rate per Unit =	5936.76							
	HEAD ROOM BEAMS	Cum							
			3	4.1	0.20	0.450	1.11		
			2	4.9	0.20	0.450	0.88		

Scanned by TapScanner

S.N	Description of work	Unit	No.	L	B	D	Qty	Rate	Amount
	Basic Rate =	5497.00					1.99	5936.76	11808.22
	Area Weightage @ 8% =	439.76							
	Total Rate per Unit =	5936.76							
23	KSR8 4.6.7: Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for sides and soffits of beams, beam haunchings, cantileven, girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (P.No.17, I.No.4.34 of PWD S.R 2018-19)								
	GROUND FLOOR	Sqm							
	B1-B4		2	19.64		0.450	17.68		
			1	19.64	0.200		3.93		
	B5-B7		2	19.64		0.450	17.68		
			1	19.64	0.200		3.93		
	B8-B9		2	10.74		0.450	9.67		
			1	10.74	0.200		2.15		
	B10 TO B11		2	4.90		0.450	4.41		
			1	4.90	0.200		0.98		
	B12 TO B16		2	19.64		0.450	17.68		
			1	19.64	0.200		3.93		
	B17		2	5.80		0.450	5.22		
			1	5.80	0.200		1.16		
	B18 TO B20		2	11.86		0.450	10.67		
			1	11.86	0.200		2.37		
	B21		2	4.40		0.450	3.96		
			1	4.40	0.200		0.88		
	B22-B23		2	6.86		0.450	6.17		
			1	6.86	0.200		1.37		
	B24		2	4.40		0.450	3.96		
			1	4.40	0.200		0.88		
	B25		2	4.40		0.450	3.96		
			1	4.40	0.200		0.88		
	B26 TO B27		2	6.86		0.450	6.17		
			1	6.86	0.200		1.37		
	B28 TO B28A		2	5.50		0.450	4.95		
			1	5.50	0.200		1.10		
	B29 TOB31		2	11.86		0.450	10.67		
			1	11.86	0.200		2.37		
	B32 TO B34		2	13.71		0.450	12.34		
			1	13.71	0.200		2.74		
	Basic Rate =	292.00					165.23	315.36	52107.25
	Area Weightage @ 8% =	23.36							
	Total Rate per Unit =	315.36							
	FIRST FLOOR	Sqm							
	B1-B4		2	19.64		0.45	17.68		
			1	19.64	0.2		3.93		

Scanned by TapScanner

S.N	Description of work	Unit	No.	L	B	D	Qty	Rate	Amount
	B5-B7		2	19.64		0.45	17.68		
			1	19.64	0.2		3.93		
	B8-B9		2	10.74		0.45	9.67		
			1	10.74	0.2		2.15		
	B10 TO B11		2	4.9		0.45	4.41		
			1	4.9	0.2		0.98		
	B12 TO B16		2	19.64		0.45	17.68		
			1	19.64	0.2		3.93		
	B18 TO B20		2	11.86		0.45	10.67		
			1	11.86	0.2		2.37		
	B21		2	4.4		0.45	3.96		
			1	4.4	0.2		0.88		
	B22-B23		2	6.86		0.45	6.17		
			1	6.86	0.2		1.37		
	B24		2	4.4		0.45	3.96		
			1	4.4	0.2		0.88		
	B25		2	4.4		0.45	3.96		
			1	4.4	0.2		0.88		
	B26 TO B27		2	6.86		0.45	6.17		
			1	6.86	0.2		1.37		
	B28A		2	3.65		0.45	3.29		
			1	3.65	0.2		0.73		
	B29 TOB31		2	11.86		0.45	10.67		
			1	11.86	0.2		2.37		
	B32A TO B34		2	11.86		0.45	10.67		
			1	11.86	0.2		2.37		
							154.78	321.84	49814.72
	Basic Rate =	292.00							
	Lift charges=	6.00							
	Area Weightage @ 8% =	23.84							
	Total Rate per Unit =	321.84							
	SECOND FLOOR	Sqm							
	B1-B4		2	19.64		0.45	17.68		
			1	19.64	0.2		3.93		
	B5-B7		2	19.64		0.45	17.68		
			1	19.64	0.2		3.93		
	B8-B9		2	10.74		0.45	9.67		
			1	10.74	0.2		2.15		
	B10 TO B11		2	4.9		0.45	4.41		
			1	4.9	0.2		0.98		
	B12 TO B16		2	19.64		0.45	17.68		
			1	19.64	0.2		3.93		
	B18 TO B20		2	11.86		0.45	10.67		
			1	11.86	0.2		2.37		

Scanned by TapScanner

S.N	Description of work	Unit	No.	L	B	D	Qty	Rate	Amount
	B21		2	4.4		0.45	3.96		
			1	4.4	0.2		0.88		
	B22-B23		2	6.86		0.45	6.17		
			1	6.86	0.2		1.37		
	B24		2	4.4		0.45	3.96		
			1	4.4	0.2		0.88		
	B25		2	4.4		0.45	3.96		
			1	4.4	0.2		0.88		
	B26 TO B27		2	6.86		0.45	6.17		
			1	6.86	0.2		1.37		
	B28A		2	3.65		0.45	3.29		
			1	3.65	0.2		0.73		
	B29 TOB31		2	11.86		0.45	10.67		
			1	11.86	0.2		2.37		
	B32A TO B34		2	11.86		0.45	10.67		
			1	11.86	0.2		2.37		
							154.78	328.32	50817.70
	Basic Rate =	292.00							
	Lift charges=	12.00							
	Area Weightage @ 8% =	24.32							
	Total Rate per Unit =	328.32							
	HEAD ROOM	Sqm							
			6	4.10		0.450	11.07		
			3	4.10	0.200		2.46		
			4	4.90		0.450	8.82		
			2	4.90	0.200		1.96		
							24.31	334.80	8138.99
	Basic Rate =	292.00							
	Lift charges=	18.00							
	Area Weightage @ 8% =	24.80							
	Total Rate per Unit =	334.80							
24	Providing and laying cement concrete using 25mm down size granite jelly of ready mixed concrte (RMC) for R.C.C works laid in 15cms thick and well compacted vibrating, curing etc.,including smooth finish cement mortar 1:3,with all lead lifts etc., complete (exclusive of cost of steel and fabrication charges) -Ready mixed cement concrete for Beams,columns,stairecase and Roof with M-25 (1:1.5:3)(page no 19 item 4.49.2 p.w.d SR 2018-19)								
	GROUND FLOOR SLAB	CUM							
			1	19.64	11.86	0.150	34.94		
			1	6.15	2.25	0.150	2.08		
	SLAB PROJECTION		1	20.00	0.45	0.150	1.35		
	Deduction Stairecase		-1	2.25	3.70	0.150	-1.25		
	lift opening		-1	2.45	3.70	0.150	-1.36		
							35.76	5936.76	212278.86
	Basic Rate =	5497.00							
	Area Weightage @ 8% =	439.76							
	Total Rate per Unit =	5936.76							
	FIRST FLOOR SLAB	CUM							
			1	19.64	11.86	0.15	34.94		
	SLAB PROJECTION		1	20.00	0.45	0.15	1.35		
	Deduction Stairecase		-2	2.25	3.70	0.150	-2.50		

Scanned by TapScanner

S.N	Description of work	Unit	No.	L	B	D	Qty	Rate	Amount
	lift opening		-1	2.45	3.70	0.150	-1.36		
							32.43	5936.76	192542.84
	Basic Rate =	5497.00							
	Area Weightage @ 8% =	439.76							
	Total Rate per Unit =	5936.76							
	SECOND FLOOR SLAB	CUM							
			1	19.64	11.86	0.15	34.94		
	SLAB PROJECTION		1	20.00	0.45	0.15	1.35		
	Deduction Stairecase		-2	2.25	3.70	0.150	-2.50		
	lift opening		-1	2.45	3.70	0.150	-1.36		
							32.43	5936.76	192542.84
	Basic Rate =	5497.00							
	Area Weightage @ 8% =	439.76							
	Total Rate per Unit =	5936.76							
	HEAD ROOM SLAB	CUM							
			1	5.30	4.10	0.150	3.26		
							3.26	5936.76	19350.87
	Basic Rate =	5497.00							
	Area Weightage @ 8% =	439.76							
	Total Rate per Unit =	5936.76							
25	KSRB 4-6.3: Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for flat surface such as suspended floors,roofs,landings,balconies and likes thickness above 200 mm including cost of all materials, labour complete as per specifications. Specification No. (P.No.16, I.No.4.30 of PWD SR 2018-19)								
	GROUND FLOOR ROOF	Sqm							
			1	19.64	11.860		232.93		
			1	6.15	2.250		13.84		
			1	20.00	0.450		9.00		
			-1	2.25	3.70		-8.33		
	Deduction Stairecase		-1	2.45	3.70		-9.07		
	lift opening						238.38	475.20	113277.18
	Basic Rate =	440.00							
	Area Weightage @ 8% =	35.20							
	Total Rate per Unit =	475.20							
	FIRST FLOOR ROOF	Sqm							
			1	19.64	11.860		232.93		
			1	20.00	0.450		9.00		
			-1	2.25	3.700		-8.33		
	Deduction Stairecase		-1	2.45	3.700		-9.07		
	lift opening						224.54	475.20	106701.60
	Basic Rate =	440.00							
	Area Weightage @ 8% =	35.20							
	Total Rate per Unit =	475.20							
	SECOND FLOOR ROOF	Sqm							
			1	19.64	11.860		232.93		
			1	20.00	0.450		9.00		
			-1	2.25	3.700		-8.33		
			-1	2.45	3.700		-9.07		
							224.54	475.20	106701.60
	Basic Rate =	440.00							
	Area Weightage @ 8% =	35.20							
	Total Rate per Unit =	475.20							
	HEAD ROOM	Sqm							
			1	5.30	4.100		21.73		
							21.73	475.20	10326.10
	Basic Rate =	440.00							
	Area Weightage @ 8% =	35.20							
	Total Rate per Unit =	475.20							
26	KSRB 15.3.13 Providing 12mm thick cement plastering in a single coat with cement mortar 1:3 to ceiling including rouding of corner wherever required smooth rendering, providing and removing scaffolding, including cost of materials, Labour, Curing complete as per specification.(Pg No 116-item No 15.21 PWD SR 2018-19)								
	GROUND FLOOR FOR CEILING	Sqm	1	19.64	11.860		232.93		

Scanned by TapScanner

S.N	Description of work	Unit	No.	L	B	D	Qty	Rate	Amount
			1	6.15	2.250		13.84		
			1	20.00	0.450		9.00		
	Deduction Stairecase		-1	2.25	3.700		-8.33		
	lift opening		-1	2.45	3.700		-9.07		
	Basic Rate =	235.00					238.38	253.80	60500.31
	Area Weightage @ 8% =	18.80							
	Total Rate per Unit =	253.80							
	FIRST FLOOR FOR CEILING	Sqm							
			1	19.64	11.86		232.93		
			1	20.00	0.45		9.00		
	Deduction Stairecase		-1	2.25	3.70		-8.33		
	lift opening		-1	2.45	3.70		-9.07		
	Basic Rate =	235.00					224.54	253.80	56988.35
	Area Weightage @ 8% =	18.80							
	Total Rate per Unit =	253.80							
	SECOND FLOOR FOR CEILING	Sqm							
			1	19.64	11.86		232.93		
			1	20.00	0.45		9.00		
	Deduction Stairecase		-1	2.25	3.70		-8.33		
	lift opening		-1	2.45	3.70		-9.07		
	Basic Rate =	235.00					224.54	253.80	56988.35
	Area Weightage @ 8% =	18.80							
	Total Rate per Unit =	253.80							
	HEAD ROOM FOR CEILING	Sqm							
			1	5.30	4.10		21.73		
	Basic Rate =	235.00					21.73	253.80	5515.07
	Area Weightage @ 8% =	18.80							
	Total Rate per Unit =	253.80							
27	KSRB 10-3: Providing and laying integral cement based **waterproofing treatment** including preparation of surface as required for treatment of roofs, balconies, terraces etc., consisting of following application. (a) Applying and grouting a slurry coat of neat cement using 2.75 kg/ sqm of cement admixed with proprietary water proofing compound conforming to IS:2645 over the RCC slab after cleaning the surface before treatment. (b) Laying cement concrete using broken brick bats 25mm to 100mm size with 50% of cement mortar 1:5 admixed with proprietary water proofing compound conforming IS:2645 over 20mm thick layer of cement mortar 1:5 admixed with proprietary water proofing compound to required slope and treating similarly the adjoining walls upto 300mm height including rounding off junctions of walls and slabs. (c) After two days of proper curing, applying a second coat of cement lurry admixed with proprietary water proofing compound (d) Finishing the surface with 20mm thick joint less cement mortar of mix 1:4 admixed with proprietary water proofing compound and finally finishing the surface with trowel and neat cement slurry and making of 300x300mm square. (e) The whole terrace so finished shall be flooded with water for a minimum period of two weeks for curing and for final test including cost of materials, labour complete as per specifications. (PWD-SR 2018-19, P-68, I-10.2)								
	Terrace floor	sqm	1	19.64	11.86		232.93		
	Head Room Terrace floor	Sqm	1	5.30	4.10		21.73		
	Deduction Stairecase		-1	2.25	3.7		-8.33		
	lift opening		-1	2.45	3.7		-9.07		
	Basic Rate =	1006.00							
	Area Weightage @ 8% =	80.48					237.27	1086.48	257789.54
	Total Rate per Unit =	1086.48							

Scanned by TapScanner

S.N	Description of work	Unit	No.	L	B	D	Qty	Rate	Amount
28	KSRB 7.9 : Providing and fixing M.S. grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications. Specification No. KBS 7.12 (page no. 34. Item no.7.9 PWD-S.R 2018-19)								
	GROUND FLOOR	sqm							
	W		1	1.80		1.20	2.16		
	W1		8	1.20		1.35	12.96		
							2.16		
					2.16 x 21 kg/sqm		45.36	102.60	4653.94
	Basic Rate =	95.00							
	Area Weightage @ 8% =	7.60							
	Total Rate per Unit =	102.60							
	FIRST FLOOR	sqm							
	W1		15	1.20		1.20	21.60		
							21.60		
					21.60 x 21 kg/sqm		453.60	102.60	46539.36
	Basic Rate =	95.00							
	Area Weightage @ 8% =	7.60							
	Total Rate per Unit =	102.60							
	SECOND FLOOR	sqm							
	W1		15	1.20		1.20	21.60		
							21.60		
					21.60 x 21 kg/sqm		453.60	102.60	46539.36
	Basic Rate =	95.00							
	Area Weightage @ 8% =	7.60							
	Total Rate per Unit =	102.60							
29	UPVC WINDOWS Providing and fixing of 3-track x 2 panel sliding windows made out of multi chambered UPVC (matching to RAL-9016) sections and with minimum TIO2(Titanium Dioxide)at 6PHR with TPV(Thermo plastic vulcanized) and lead free, gaskets-grey colour having isolated drainageand reinforced with galvanized iron profile through out the window frame.The outer frame having a overall size of108mm width x 45mm height with reinforcement of 1mm thickness and sash with overall size of 39mm x 75mm with UPVC honeycomb structureinside in lieu of GI reinforcement. Glazing bead for fixing of glass shall be a size of 20mm x 24mm. windows shall be provided with 5mm plain float glass, standard hardware and singlr point locking system with crescent locks, wall thickness of frame and sash shall beof 2mm to 2.5mm. Maximum possible size 2419mm x 2119mm. (page no. 309. Item no.38.44.7 PWD-S.R 2018-19)								
	GROUND FLOOR	sqm							
	W		1	1.80		1.20	2.16		
	W1		8	1.20		1.35	12.96		
	V		10	0.60		0.45	2.70		
	Basic Rate =	5675.00					17.82	6129.00	109218.78
	Area Weightage @ 8% =	454.00							
	Total Rate per Unit =	6129.00							
	FIRST FLOOR	sqm							
	W1		15	1.20		1.35	24.30		

Scanned by TapScanner

S.N	Description of work	Unit	No.	L	B	D	Qty	Rate	Amount
	V		8	0.60		0.45	2.16		
	Basic Rate =	5675.00					26.46	6129.00	162173.34
	Area Weightage @ 8% =	454.00							
	Total Rate per Unit =	6129.00							
	SECOND FLOOR	sqm							
	W1		15	1.20		1.35	24.30		
	V		10	0.60		0.45	2.70		
	Basic Rate =	5675.00					27.00	6129.00	165483.00
	Area Weightage @ 8% =	454.00							
	Total Rate per Unit =	6129.00							
30	KSRB15-3.6 : Providing 15 mm thick cement plaster in single coat with Cement Mortar 1:6 to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete.(P.115 I No.15.14 PWD-S.R 2018-19)(INSIDE)								
	GROUND FLOOR	SQM							
	Horizontal walls		1	19.64		3.00	58.92		
	Horizontal walls		2	10.94		3.00	65.64		
	Horizontal walls		2	10.94		3.00	65.64		
	Horizontal walls		1	16.25		3.00	48.75		
	Horizontal walls		1	3.30		3.00	9.90		
	Vertical walls		2	11.86		3.00	71.18		
	Vertical walls		12	4.40		3.00	158.40		
	Vertical walls		2	4.00		3.00	24.00		
	Vertical walls		1	4.80		3.00	14.40		
	Horizontal walls		6	2.5		3.00	45.00		
	Horizontal walls		4	2.6		3.00	31.20		
	Vertical walls		8	1.5		3.00	36.00		
	Vertical walls		2	3.5		3.00	21.00		
	DEDUCTIONS								
	FOR GROUND FLOOR								
	ED		-1	3.50		2.10	-7.35		
	D		-3	1.20		2.10	-7.56		
	D1		-4	0.90		2.10	-7.56		
	W		-1	1.80		1.20	-2.16		
	W1		-8	1.20		1.35	-12.96		
	V		-10	0.60		0.45	-2.70		
	D2		-7	0.75		2.10	-11.03		
	Basic Rate =	208.00					598.72	224.64	134496.24
	Area Weightage @ 8% =	16.64							
	Total Rate per Unit =	224.64							
	FIRST FLOOR	SQM							
	Horizontal walls		6	19.64		3.00	353.52		
	Horizontal walls		2	10.94		3.00	65.64		
	Vertical walls		4	11.86		3.00	142.37		
	Vertical walls		14	4.40		3.00	184.80		
	Vertical walls		2	4.00		3.00	24.00		
	Horizontal walls		6	4.60		3.00	82.80		
	Horizontal walls		6	3.60		3.00	64.80		
	Vertical walls		12	3.00		3.00	108.00		

Scanned by TapScanner

S.N	Description of work	Unit	No.	L	B	D	Qty	Rate	Amount
	DEDUCTIONS								
	FOR FIRST FLOOR								
	D		-1.0	1.20		2.10	-2.52		
	D1		-6.0	0.90		2.10	-11.34		
	W1		-15.0	1.20		1.35	-24.3		
	V		-8.0	0.60		0.45	-2.16		
	D2		-6.0	0.75		2.10	-9.45		
	Basic Rate =	208.00					976.16	224.64	219284.13
	Area Weightage @ 8% =	16.64							
	Total Rate per Unit =	224.64							
	SECOND FLOOR	SQM							
	Horizontal walls		6	19.64		3.00	353.52		
	Horizontal walls		2	10.94		3.00	65.64		
	Horizontal walls		2	3.30		3.00	19.80		
	Vertical walls		4	11.86		3.00	142.32		
	Vertical walls		10	4.40		3.00	132.00		
	Vertical walls		2	4.00		3.00	24.00		
	Horizontal walls		8	2.30		3.00	55.20		
	Horizontal walls		6	1.80		3.00	32.40		
	Vertical walls		14	1.50		3.00	63.00		
	DEDUCTIONS								
	FOR FIRST FLOOR								
	D		-2	1.20		2.10	-5.04		
	D1		-4	0.90		2.10	-7.56		
	W1		-15	1.20		1.35	-24.30		
	V		-10	0.60		0.45	-2.70		
	D2		-7	0.75		2.10	-11.03		
	Basic Rate =	208.00					837.26	224.64	188080.96
	Area Weightage @ 8% =	16.64							
	Total Rate per Unit =	224.64							
	HEAD ROOM								
	Horizontal walls		4	4.9		2.55	49.98		
	Horizontal walls		4	3.65		2.55	37.23		
	DEDUCTIONS		-2	0.9		2.1	-3.78		
	Basic Rate =	208.00					83.43	224.64	18741.72
	Area Weightage @ 8% =	16.64							
	Total Rate per Unit =	224.64							
31	KSRB 15-7: Providing lime rendering for plastering to wall and ceiling. including cost of materials. labour. curing complete as per specifications. (page no.117. item no.15.33 S.R 2018-19)								
	Ground Floor								
	Same qty as per inside wall pastering work	Sqm					598.72		
	Basic Rate =	32.00							
	Area Weightage @ 8% =	2.56				Total Qty	598.72	34.56	20691.73
	Total Rate per Unit =	34.56							
	First Floor								
	Same qty as per inside wall pastering work	Sqm					976.16		
	Basic Rate =	32.00							
	Lift charges=	6.00							
	Area Weightage @ 8% =	3.04				Total Qty	976.16	41.04	40061.52

Scanned by TapScanner

S.N	Description of work	Unit	No.	L	B	D	Qty	Rate	Amount
	Total Rate per Unit =		41.04						
	Second Floor								
	Same qty as per inside wall painting work	Sqm					837.36		
	Basic Rate =		32.00						
	Lift charges=		12.00						
	Area Weightage @ 8% =		3.52			Total Qty	837.36	47.52	39786.38
	Total Rate per Unit =		47.52						
	Third Room								
	Same qty as per inside wall painting work	Sqm					83.43		
	Basic Rate =		32.00						
	Lift charges=		18.00						
	Area Weightage @ 8% =		4.00			Total Qty	83.43	54.00	4505.22
	Total Rate per Unit =		54.00						
32	KSR-15.3.8 Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding of corners wherever required smooth rendering, providing and removing scaffolding, including cost of all materials, labours, curing, complete as per specifications (Pg No 116-I.No 15.16 S.R 2018-19) (outer)								
	Ground Floor	sqm							
			1	19.64		3.00	58.92		
			1	16.25		3.00	48.75		
			2	11.86		3.00	71.18		
			1	4.40		3.00	13.20		
	DEDUCTIONS								
	ED		-1	3.50		2.10	-7.35		
	D		-3	1.20		2.10	-7.56		
	D1		-4	0.90		2.10	-7.56		
	W		-1	1.80		1.20	-2.16		
	W1		-8	1.20		1.35	-12.96		
	Basic Rate =		261.00				154.46	281.88	43540.31
	Area Weightage @ 8% =		20.88						
	Total Rate per Unit =		281.88						
	First Floor	sqm							
			1	19.64		3.00	58.92		
			1	10.94		3.00	32.82		
			2	11.86		3.00	71.18		
			1	4.40		3.00	13.20		
	DEDUCTIONS								
	W1		-15	1.20		1.35	-24.30		
	V		-8	0.60		0.45	-2.16		
	Basic Rate =		261.00				149.66	281.88	42187.29
	Area Weightage @ 8% =		20.88						
	Total Rate per Unit =		281.88						
	Second Floor	sqm							
			1	19.64		3.00	58.92		
			1	10.94		3.00	32.82		
			2	11.86		3.00	71.16		
			1	4.40		3.00	13.20		

Scanned by TapScanner

S.N	Description of work	Unit	No.	L	B	D	QTY	Rate	Amount
	DEDUCTIONS								
	Wt								
	V		15	1.20		1.33	24.30		
			10	0.60		0.45	2.70		42028.81
	Basic Rate =	261.00					149.10	281.88	
	Area Weightage @ 8% =	20.88							
	Total Rate per Unit =	281.88							
	Terrace Floor								
	Horizontal walls	sqm							
	Vertical walls		2	4.90		3.00	29.40		
	Deduction		2	3.65		3.00	21.90		
	D								
			2	1.20		2.10	5.04		18089.77
	Basic Rate =	261.00					46.26	281.88	
	Area Weightage @ 8% =	20.88							
	Total Rate per Unit =	281.88							
33	KSRB 15.7: Providing lime rendering for plastering to wall and ceiling, including cost of material, labour, curing complete as per specifications. (page no.117, item no.15.33 S.R 2018-19)								
	Ground Floor								
	Same qty as per outside wall pastering work	Sqm					154.45		
	Basic Rate =	32.00							
	Area Weightage @ 8% =	2.56				Total Qty	154.45	34.56	5338.28
	Total Rate per Unit =	34.56							
	First Floor								
	Same qty as per outside wall pastering work	Sqm					149.65		
	Basic Rate =	32.00							
	Area Weightage @ 8% =	2.56				Total Qty	149.65	34.56	5172.39
	Total Rate per Unit =	34.56							
	Second Floor								
	Same qty as per outside wall pastering work	Sqm					149.10		
	Basic Rate =	32.00							
	Area Weightage @ 8% =	2.56				Total Qty	149.10	34.56	5152.90
	Total Rate per Unit =	34.56							
	Terrace Floor								
	Same qty as per outside wall pastering work	Sqm					46.26		
	Basic Rate =	32.00							
	Area Weightage @ 8% =	2.56				Total Qty	46.26	34.56	1598.75
	Total Rate per Unit =	34.56							
34	KSRB 15.3.13 Providing 12mm thick cement plastering in a single coat with cement mortar 1:3 to ceiling including rouding of corner wherever required smooth rendering, providing and removing scaffolding, including cost of materials, Labour, Curing complete as per specification.(Pg No 116-item No 15.21) PWD 2018-19)								
	Ground Floor	Sqm							
	Qty as per of centring of staire						15.25		
	Basic Rate =	235.00					15.25	253.80	3870.35
	Area Weightage @8% =	18.80							
	Total Rate per Unit =	253.80							
	First Floor	Sqm							
	Qty as per of centring of staire						15.25		

Scanned by TapScanner

S.N	Description of work	Unit	No.	L	B	D	Qty	Rate	Amount
	Basic Rate =		235.00				15.25	253.80	3870.35
	Area Weightage @8% =		18.80						
	Total Rate per Unit =		253.80						
	Second Floor	Sqm							
	Qty as per of centring of staire						15.25		3870.35
	Basic Rate =		235.00				15.25	253.80	
	Area Weightage @8% =		18.80						
	Total Rate per Unit =		253.80						
	Head Room	Sqm							
	Qty as per of centring of staire						15.25		3870.35
	Basic Rate =		235.00				15.25	253.80	
	Area Weightage @8% =		18.80						
	Total Rate per Unit =		253.80						
35	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and achoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No.KBS 4.6.3 (P.No.18, I.No.4.46.2 of PWD SR 2018-19)								
	Ground Floor								
	Footings	Tonne		67.87	kg/cum	120	8143.92		
	lintels			4.82	kg/cum	75	361.24		
	Columns			51.57	kg/cum	140	7219.45		
	Plinth beams			15.16	kg/cum	110	1667.60		
	Roof beams			40.84	kg/cum	130	5308.64		
	Roof			103.88	kg/cum	100	10388.08		
							33088.93		
	Basic Rate =		70966.00				33.09	76643.28	2536044.26
	Area Weightage @ 8% =		5677.28						
	Total Rate per Unit =		76643.28						
36	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH -100/ Chapter 1 (PWD - SR 2018-19, P-115, I-17.1) M100-4.1, Cost of Haulage Excluding Loading and Unloading MORTH -100/ Chapter 1 Case-I : Surface Road (PWD -SZB-SR 2016-17, P-134, I-17.4) lead taken - 15 km = Rs 2.5 t/km = (basic rate + area weightage) x 15 km = 67.50 (debris density 1.3 tonne/cum)								
	loading,unloading & haulage of dismantling quantity						77.93	Cum	114.21	8900.88
	Basic rate loading		57.00						
	Area weightage 8%		4.56						
	Basic rate haulage 15km lead taken in cum	t/km	48.75	in cum 2.5 x 1.3 x 15					
	Area weightage		3.90						
	Total		114.21				252.37	tonne	40.50	10220.99
	haulage of marshy soil & ordinary soil								
	Basic rate - haulage 15km lead taken	t/km	37.50	(2.5 x 15)					
	Area weightage		3.00						
	Total		40.50						

Scanned by TapScanner